| ESTIMATE FOR THE ELECTRICAL WORK OF HPGB BANK | | | | | |
|---|---|---|---|---|---|
| **Sr. No.** | **Discription** | **Unit** | **Quantity** | **Rate in Rs.** | **Amount in Rs.** |
| **B** | **ELECTRICAL** | | | | |
| 1 | Providing installing testing& commissioning of pre wired recessed/Surfece Type fixture of approved model & make With Switches as approved by Architect comprising of powder coated body & steel reflector inside complete with holder etc with copper wiring as required( Syska Cromption PhilipsHavels)Syska LED45 watt 2x2 | Nos. | 6 | 3200 | 19200.00 |
| 2 | Providing & fixing LED Down Lighter 18 Watt 6" dia | Nos. | 2 | 950 | 1900.00 |
| 3 | Providing & Fixing wall iron body Metal fans Complete with switches: Bajaj / Crompton Greaves / Almonard | Nos. | 3 | 4500 | 13500.00 |
| 4 | SITC of 300 mm exhaust metal fans 1400 rpm (Double ball bearing) Heavy duty Crompton Greaves / Phillips.complete with self opening louvers/shutters etc. complete with suitable wooden/iron frame as reqd | Nos. | 3 | 2850 | 8550.00 |
| 5 | 24 Whatt LED TUBE Ligthts with all fittings (Crompton Greaves / Phillips. | Nos. | 4 | 375 | 1500.00 |
| 6 | ELECTRICAL POINTS :<br>Providing laying fixing & testing of electrical points including wiring from MCB's to switches plate type switches socket & M.S. Modular boxes with rust proof treatment size to accommodate the required nos. of switches & sockets plus circuit wiring from switches to lights/fans/fixtures etc. wherever required complete with earthing 1.00 mm2 multi strand wire in 25mm dia. Unbreakable PVC conduit Diplast with specials under floor / wall & above false ceiling or making truff under / along work – stations including chase cutting disposal of melba away from the site and repair of the same with cement mortar copper conductor wires 2.5 Sqm only will be used of approved make.Modular switchesapproved by Bank/Architect | | | | |
| a | Electrical wiring for UPS (charging point for UPS): P / F 2 runs of 4mm sq. and one run of 1.5 sq. mm as earth wire multi-strand PVC copper wires from D/B to the location of UPS room for input to UPS in PVC pipe with DP's or 2 No's Set (15 Amp. Power plugs and sockets each set.) branch | Job | LS | 1500 | 1500.00 |
| b | 5 Amp plug point wiring with 1.5mm sq. multi stand PVC copper wire inc. Plate switches sockets plugs. Etc Complete in all respects. Modular switches approved by Bank/Architect | No's | 4 | 350 | 1400.00 |
| c | 15 Amp wiring with 2.5mm sq. multi strand PVC copper wire & metal clad enclosure sockets switches & plugs Complete in all respectsModular switches approved by Bank/Architect | No's | 4 | 3250 | 13000.00 |
| d | Providing and fixing of PVC conduit in wall floor including **Telephone wire**, M.S. box and two pin telephone sockets or R.J. – 11 plates out let incl. Testing and commissioning etc. as required. | No's | 2 | 450 | 900.00 |
| e | Supplying and installation (Testing connection & commissioning with 2.5 sq. mm earth wire) of earth stations for computers with 600 mm x 600 mm x 3mm th. Copper plate electrode complete with 25mm dia. "B" Class G.I. pipe for watering including funnel 30cm x 30cm x 30 cm masonry chamber with precasted RCC cover / C.I. cover complete with salt & charcoal filling (as per IS: 3034-1987) incl. copper strip 1" wide 4mm th. with copper base plate up to UPS cabin. | 1UPS (Copper) | 1 | 19000 | 19000.00 |
| | | 1 E.I. Pannel (Aluminium) | 1 | 12500 | 12500.00 |
| 7 | UPS POINTS:- P/L & testing electrical three point wiring /circuit wiring having individual circuits for computers with 2.5mm2 Multi-strand copper PVC wire in unbreakable PVC conduits 25mm dia wall thickness 2mm thick with specials under floor / wall & above false ceiling including chase cutting disposal of malba away from the site and repair of the same with cement mortar incl. Switches & socket M.S. switch boxes with rust proof treatment size to accommodate the required nos. of Modular switches sockets etc. & plate type sockets with indicator three in one plate including earthing with 1.00 mm2 multi strand wire complete in all respect | | | | |

| | | | | | |
|---|---|---|---|---|---|
| a | Set of 6 amp. 4 sockets & 4 switches **Modular switches approved by Bank/Architect** | Each set | 4 | 1500 | 6000.00 |
| b | UPS supply to tube lights: Point wiring / circuit wiring with 1.5mm sq. from D/B to switches & fittings multi strand PVC copper wire including plate switches sockets etc. (for payment no. of switches shall be counted).Modular switches approved by Bank/Architect | Nos. | 3 | 1500 | 4500.00 |
| 8 | **Providing & fixing main electrical dist. Board with all internal Electrical and Generator connections with 6 sq.mm multi strand copper wire which shall include all following items.** | Rmt | 40 | 120 | 480.00 |
| | 16-way D/B TPN of Havells make with MCBs 32 Amp. For lights fans. | Nos. | 1 | 7900 | 7900.00 |
| | 8-way single phase D/B of Havells make with MCB's and DP switch for UPS supply to computers. | Nos. | 2 | 3500 | 7000.00 |
| | Kit-kats 100 Amp. | Nos. | 4 | 250 | 1000.00 |
| 9 | Providing fixing of light Points complete in all respects. Modular switches approved by Bank/Architect | Nos. | 25 | 1500 | 37500.00 |
| 10 | Providing & fixing main electrical pvcarmoured cable 4- core al. cable armored 25mm dia.( POLYCAB) | Mtr. | 15 | 280 | 4200.00 |
| | **Total** | | | | |
| | **Extra Item As Per Requirement Networking D Link Or SS Make** | | | | |
| 11 | Rj Cat6 Networking cabel With I/O Box I/C PVC Condut Pipe & All Assosres | Nos. | 5 | 1050 | 5250 |
| 12 | Extation Leed Cat 6 I/c Rj 45 Conetor Lenth Of 105 Mtr | Nos. | 5 | 100 | 500.00 |
| | | | | **Total** | **167280.00** |